Head	Item of work	Per	Quantity
Waste-weirs—			
Left waste-weir, 120 feet long.	Blasting and benching rock...	Lump	sum.
	Burnt brick in surki mortar	C. ft.	2,645
	Burnt stone slabs	S. ft.	378
	Plastering with surki mortar	Sqr.	21·10
	Earthwork, hard soil and soft rock	C. yd.	4,313
Right waste-weir, length 240 ft.	Burnt brick in surki mortar	C. ft.	2,088
	Burnt stone slabs	S. ft.	2,801
	Plastering with surki mortar	Sqr.	12·76
	Rough stone work, new	C. yd.	697
	Concrete below slabbed apron	C. ft.	482
Raising the rood in the bed of tank.	Earthwork	C. yd.	9,554
	Turfing	S. yd.	5,159
	Raising tunnel of one vent $3\frac{1}{2} \times 5\frac{1}{4}$	Lump	sum.
	Burnt stone in chunam	C. ft.	184
	Old stone in chunam	,,	41
	Pointing with chunam	Sqr.	1·61
	Rough stone work	C. yd.	16
Raising tunnel of one vent $2 \times 2\frac{3}{4}$	Removing and re-fixing covering slabs... ...	S. ft.	105
	Burnt stone in chunam	C. ft.	167
	Old stone in chunam	C. ft.	26
	Pointing with chunam	Sqr.	1·43
	Rough stone work	C. yd.	12
	Removing and re-fixing stone slabs	S. ft.	84
Raising tunnel of three vent $4\frac{1}{2} \times 4$	Burnt stone in chunam	C. ft.	191
	Old stone in chunam	,,	128
	Pointing with chunam	Sqr.	3·15
	Rough stone work	C. yd.	16
	Removing and re-fixing covering slabs ...	S. ft.	388
	Making temporary rood	Lump	sum.
	Collecting and stocking burnt stone metal ...	C. yd.	385
	Carting metal, 1½ mile lead	,,	385
	Collection of gravel	,,	70
	Carting do ½ mile lead	,,	70
	Picking road way	S. yd.	3,080
	Spreading metal	C. yd.	385
	Do gravel	,,	70
	Collecting and spreading sand	,,	11
	Benching rock	Lump	sum.
Feeder channel—	Earthwork throwing a flank bund	C. yd.	156
	Rough stone wing on right and left	,,	15
	Concrete in chunam	C. ft.	400
	Burnt brick in surki mortar	,,	1,370
	Surki plastering	Sqr.	5·15
	Burnt stone slabs	S. ft.	1,127
	Banking to a length of 150 yards	C. yd.	1,000
	Do rough stone revetment	,,	300
	Constructing 15' long lifting dam and inserting a 9" pipe in weir.	Lump	sum.
	Removing short bund of reservoir	,,	
	Clearing draft in feeder channel	C. yd.	222
	Concrete below slabbed apron	C. ft.	238

K. KRISHNA IYENGAR, *Executive Engineer.*

SHIMOGA DIVISION.

Notification dated 9th January 1906.

In the Court of the Assistant Commissioner and 1st Class Magistrate, Shimoga Division.

Any person that may have a claim to any of the articles, a detailed list of which was published in the Gazette No. 3, dated 18th January 1906, should appear in person and establish his claim within six months from the date of the said notification.

K. CHANDY,

Asst. Comr. & 1st Class Magistrate.